

City of El Paso - City Plan Commission Staff Report

Case No: SUSC14-00002 Montecillo #4 Replat A (Reconsideration)

Application Type: Resubdivision Final **CPC Hearing Date:** October 8, 2015

Staff Planner: Nelson Ortiz, (915) 212-1606, ortiznx@elpasotexas.gov

Location: West of Mesa and North of Castellano

Acreage: 10.067 acres

Rep District: 8

Existing Use: Vacant

Existing Zoning: SCZ (Smartcode; T4, T4O, T5) **Proposed Zoning:** SCZ (Smartcode; T4, T4O, T5)

Nearest Park: Galatzan Park (0.62 mile)

Nearest School: Morehead Middle School (0.61 mile)

Park Fees Required: N/A Impact Fee Area: N/A

Property Owner: EPT Montecillo Development East, LP **Applicant:** EPT Montecillo Development East, LP

Representative: Conde, Inc.

SURROUNDING ZONING AND LAND USE

North: R-3 / Residential Development

South: SCZ / Vacant East: SCZ / Vacant West: SCZ / Vacant

PLAN EL PASO DESIGNATION: G2 Traditional Neighborhood (Walkable)

APPLICATION DESCRIPTION

The applicant proposes to subdivide 10.067 acres of vacant land. Thirty-three residential lots intended for townhomes and a .16 acre civic space "Promontory with Gazebo" are proposed within this phase of the subdivision. Primary access to the subdivision is proposed from Montecillo Boulevard. This application is being reviewed under Title 21 (SmartCode) and does comply with the approved Montecillo Regulating Plan.

CASE HISTORY and REQUEST

- The City Plan Commission, at its regular meeting of November 21, 2013, voted to approve Montecillo Unit Four on a Major Preliminary basis.
- On April 10, 2014, the City Plan Commission approved Montecillo Unit Four Replat A
 which excluded the commercial lots and a .789 acre green space from the approved
 Major Preliminary.

SUSC14-00002 1 October 8, 2015

- On July 16, 2015, the City Plan Commission approved Montecillo Unit Four Replat A which included widened ROWs in order to accommodate landscaped parkways.
- With this application, the applicant is seeking re-approval of Montecillo Unit Four Replat A (final plat) which provides revised Park comments related to the Promontory space.

DEVELOPMENT COORDINATING COMMITTEE

The Development Coordinating Committee recommends **re-approval** of Montecillo Unit Four Replat A on a Resubdivision Final basis, subject to the following comments.

Planning Division Recommendation:

Approval subject to the following:

• In accordance with Section 19.15.070.A (Intersections, half-streets), all street intersections shall be situated at an angle of ninety degrees, plus or minus fifteen degrees and must maintain intersection visibility as determined by the latest edition of AASHTO's "A policy on Geometric Design of Highways and Streets." (Visibility cannot be determined until submittal of the improvement plans.)

Long Range Planning

No objections.

Land Development

We have reviewed subject plats and recommend **Approval**.

The Developer/Engineer shall address the following comments.

1. EPDOT review and approval is required for proposed ROW slope easements.

Parks and Recreation

We have **re-**reviewed **Montecillo Unit Four "A"**, a revised resubdivision final plat map and on behalf of CID Parks Planning Division we offer Developer / Engineer the following comments:

This subdivision is zoned "SCZ" (Smart Code Zoning) therefore not required to comply with the parkland dedication ordinance Title 19 – Subdivision & Development Plats, **Chapter 19.20 - Parks & Open Space**, however, applicant needs to comply with Title 21 Smart Code Civic Space requirements.

Parks have no objections to this subdivision application; however, based on the approved "Montecillo Development Regulating Plan" we offer the following comments:

- 1. Promontory area shall be developed per approved Regulating Plan and Title 21 Standards.
- 2. Developer (EPT) in addition to the approved Regulating Plan improvements to the Promontory area agrees to provide a Gazebo, some park benches as well as a garden wall 4'- 6' high combination rock wall / wrought iron abutting the arroyo.

This Development is with-in Park Zone: NW-2

Nearest Parks: Galatzan & Crestmont

El Paso Water Utilities

1. EPWU does not object to this request.

Water

2. The subdivision requires the extension of an 8-inch diameter water main along the alignment of Vin Castellano Dr. from the existing 8-inch diameter water main located on Castellano

- Drive (approximately 340-ft west of the intersection of Montecillo Dr. and Castellano Dr.) to connect to the existing 8-inch diameter water main along Festival Dr.
- 3. The subdivision will be located within an intermediate pressure zone. Private water pressure regulating devices will be required at every lot within the intermediate pressure zone. The Developer shall include in the sale of contract documents that the lot/home buyer shall acquire ownership of the above-described water pressure regulating devices to be located at the discharge side of the water meters. The lot/home buyer shall be responsible for the operation and maintenance of the above-described water pressure regulating devices.

Sanitary Sewer

4. The subdivision requires the extension of an 8-inch diameter gravity sanitary sewer main along Vin Castellano Dr. to connect to an existing 8-inch diameter gravity sewer main located within a P.S.B. Easement located across Vin Castellano Dr.

General:

- 5. The water and sanitary sewer mains mentioned above are required to be installed and accepted by EPWU-PSB prior to providing service to the subject property.
- 6. EPWU requires a new service application to provide service for the proposed subdivision. New service applications are available at 1154 Hawkins, 3rd Floor. The following items are required at the time of application: (1) hard copy of subdivision plat; (2) finalized set of street improvement plans, including storm sewer; (3) digital copy of subdivision plat; (4) benchmark check; and (5) construction schedule. Service will be provided in accordance with the current EPWU PSB Rules and Regulations. The owner is responsible for the costs of any necessary on-site and off-site extensions, relocations or adjustments of water and sanitary sewer lines and appurtenance.

Sun Metro:


No comments received.

Additional Requirements and General Comments:


- 1. Submit to the Planning and Inspections Department Planning Division the following prior to recording of the subdivision.
 - a. Current certified tax certificate(s)
 - b. Current proof of ownership
 - c. Release of access document, if applicable
 - d. Set of restrictive covenants, if applicable
- 2. Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.

Attachments

- 1. Location map
- 2. Aerial map
- 3. Final plat
- 4. Application



MONTECILLO UNIT FOUR REPLAT 'A' MONTE VALUE MONTE SOL MONTECILO





CITY PLAN COMMISSION APPLICATION FOR RESUBDIVISION FINAL SUBDIVISION APPROVAL

	DATE: June 15, 2015	File No		<u>.</u>				
	SUBDIVISION NAME: Montecillo Unit 4 Replat "A"			<u>.</u>				
1.	Legal Description for the area included on this plat (Tract, Blo Being a Replat of a Portion of Lots 3 and 6, Block 2, Mo John Barker Survey 10, City of El Paso, El Paso County,	ntecillo Unit Three Replat	"B", and portion of					
2.	Proposed Land Uses:		ACRES	SITES				
	Single-family ACRES SITES	Office	ACKES	311123				
	Duplex	Street & Alley	2.012	<u> </u>				
	Apartment	Ponding & Drainage	200					
	Mobile Home	Institutional						
	P.U.D.	Other (specify below)						
		Town Homes	7.8954	33				
	Park	Promontory	0.1506	1 .				
	School		0.1500	<u> </u>				
	Commercial	Total No. Sites 35	10.050					
	Industrial	Total Acres (Gross)	10.058					
3.	What is existing zoning of the above described property? Solution	martCode	Proposed zoning?	n/a				
4.	Will the residential sites, as proposed, permit development in f	ull compliance with all zoning	g requirements of the ex	cisting residential				
	zone(s)? Yes_X No							
5.	What type of utility easements are proposed? UndergroundOverheadCombination of BothX_							
6.	What type of drainage is proposed? (If applicable, list more than one) Lot to street to Drainage Structure							
7.	Are special public improvements proposed in connection with the development? YesNoX							
8.	Is a modification or exception of any portion of the Subdivision Ordinance proposed? YesNoX If answer to is "Yes", please explain the nature of the modification or exception							
9.	Remarks and/or explanation of special circumstances:							
10.	Improvement Plans submitted? YesX	No						
		and do not be about this area. He address	in subject to the stead of	anda in afficul maior to d				
11.	Will the proposed subdivision require the city to review and decide whether this application is subject to the standards in effect prior to effective date of the current applicable standards? YesNoX							
	If yes, please submit a vested rights petition in accordance wit	th Title 1 (General Provisions)	Chanter 1.04 - Vested	Rights				
	ii yoo, picaso sabaat a resea i gato pentoli ii aeeesaasee	,	,					
	City Develor	oment Department						
	811 Texas P.O. Box 1890 El Pa	so, Texas 79950-1890 (91	5) 212-0085.					

12.	Owner of record	EPT Montecillo Developme	ent East, L.P. 8201 Lockheed, El Paso,	TX 79925	779-7271	
		(Name & Address)		(Zip)	(Phone)	
13.	Developer_EP	Montecillo Development E	ast, L.P. 8201 Lockheed, El Paso, TX	79925	779-7271	
		(Name & Address)		(Zip)	(Phone)	
14.	Engineer	CONDE INC.	6080 Surety Drive, Ste 100, El Paso, TX	79905	915-592-0283	
		(Name & Addr	ress)	(Zip)	(Phone)	

*Effective September 1, 2014, a 3% Technology fee has been added to all Planning application fees.

EPT Montecillo Development East, L.P. A Texas Limited Liability Company By It's General Partner

EPT Montecillo Development Management, LLC A Texas Limited Liability Company

OWNER SIGNATURE:

Richard Aguilar, Manager

REPRESENTATIVE:

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS